Cornerstone Construction Company

17615 Alder St Ste A Hesperia, CA 92345 (760) 503-5545 cc@cornerstone.dev



ADDRESS

Robert Saffell Silver Valley Unified School District 35320 Daggett-Yermo Rd Yermo, CA Proposal 1199

DATE 09/08/2022

EXPIRATION DATE 10/07/2022

PROJECT NAME

SVHS - Ball Field Wind Fence

CONTRACTITEM	DECORIDATION	OTV	DATE	AMOUNT
CONTRACT ITEM	DESCRIPTION	QTY	RATE	AMOUNT
Fencing	Provide all labor, material, and equipment necessary to install fencing pursuant to description below. All work shall meet or exceed any applicable jurisdictional building codes. This excludes all jurisdictional permit fees. - 375' of 8' private-link installed on west side of ball fields for wind block. Post will be set on 7' centers due to the wind load. All corner post will be sch 40 -4" and line post will be 2-7/8".	1	39,000.00	39,000.00
Concrete Curb	Install concrete curbing per description: - 375' of concrete curb 18" wide by 6" thick installed along/ beneath private-link fence. Concrete will be 3,000 psi.	1	25,000.00	25,000.00

CONTRACT ITEM	DESCRIPTION	QTY	RATE	AMOUNT	
General Provision	Management of the jobsite, SWPP implementation and maintenance, insurance, administrative support. - Excludes Engineered Traffic Control Plans or set upsonly basic flag and cone included - Excludes Geotech services - Excludes permitting - Excludes excavation greater than (2)' deep on ALL line items and/or the specified depth listed per contract item. - Excludes survey - Excludes union wages - Excludes excavation of large rock (8"D and greater) or hard/sandy/very wet soil - Excludes deposal of trench spoils - Excludes ALL demo and patch back of any surface (landscape, asphalt, concrete sidewalk, etc.) except that clearly listed in the cost proposal. - Legal source of water must be at the project location (within 1500' not requiring traffic control for use) - Equipment, and material to be stored onsite for duration of mobilization. - Free parking must be provided for up to 10 cars & or trailers on a daily basis - Basic BMPs included - Includes basic non-engineered shoring needed to complete basic installation. PAYMENT AND PERFORMANCE BOND INCLUDED	1	2,900.00	2,900.00	

Please review the attachments that were sent with this estimate as they may effect the way we conduct business together. We are excited to earn your business!

TOTAL \$66,900.00

Accepted By Accepted Date